

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

All provisions of the New Mexico State Highway and Transportation Department's Standard Specifications for Highway and Bridge Construction, edition of 2019 shall apply except as modified herein.

<u>DESCRIPTION</u>	<u>PAGE</u>
MODIFYING SECTION 201 - CLEARING AND GRUBBING	2
DELETING SECTION 303 – BASE COURSE.....	2
ADDING AND MODIFYING SECTION 247 – FLEXIBLE BASE	2
MODIFYING SECTION 407 - TACK COAT	3
ADDING SECTION 409 - AGGREGATE PRIMER	4
MODIFYING SECTION 423 - HOT MIX ASPHALT	5
ADDING SECTION 499 - CHIPSEAL.....	6
APPENDIX	8
• TXDOT SECTION 247 – FLEXIBLE BASE	

Wherever the word Department is found replace with Owner. The Project Manager is the Owner's representative who is delegated the responsibility for the administration of the project.

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

MODIFYING SECTION 201 - CLEARING AND GRUBBING

Delete subsections 201.4 and 201.5 and substitute the following:

201.4 METHOD OF MEASUREMENT

Clearing and grubbing will be measured by the acre unit.

201.5 BASIS OF PAYMENT

Item Number	Description	Unit
201000	<i>Clearing and Grubbing</i>	Acre

DELETING SECTION 303 – BASE COURSE

Delete section 303 in its entirety.

ADDING AND MODIFYING SECTION 247 – FLEXIBLE BASE

Add the Texas Department of Transportation (TxDOT) section 247 included in Appendix. Make the following modifications to the 247 specification.

2. MATERIALS

The base course material shall be Flexible Base, Grade 3, Type E (10" thickness) with maximum Aggregate Index (AI) of 35.

4.3. Compaction

Delete sub-section 4.3. and replace with:

Compact base course to at least 96% of maximum density as determined by AASHTO T 180 (Modified Proctor), Method D (TTCP Modified).

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

5. MEASUREMENT

Delete Section 5 and replace with:
Flexible base will be measured by the square yard unit.

6. PAYMENT

Delete Section 6 and replace with:
10" Flexible Base will be paid for by square yard.

Item Number	Description	Unit
303210	<i>10" Flexible Base</i>	S.Y.

MODIFYING SECTION 407 - TACK COAT

Delete subsection 407.4 and replace with the following:

407.4 METHOD OF MEASUREMENT

407.4.1 Bituminous material for tack coat will be measured by the square yard. Estimated application rates to range from 0.06 to 0.10 gallons per square yard.

407.5 BASIS OF PAYMENT

407.5.1 Bituminous material for tack coat will be paid for at the contract unit price per square yard.

Payment will be made under:

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

Item Number	Description	Unit
407000	<i>Asphalt Material for Tack Coat</i>	S.Y.

Separate payment will not be made for water added on site to further dilute emulsified asphalts. Any tack placed on existing concrete curbs, sidewalks, medians or pavements shall be cleaned and removed. No separate payment or measurement will be made for this work.

ADDING SECTION 409 - AGGREGATE PRIMER

ADD the following:

- 409.1 This work shall consist of placing Aggregate Primer on top of flexible base course. The contractor shall provide bituminous material. The Contractor shall supply and apply approximately 8 lb/ft² 3/8" aggregate to the bituminous material. The Contractor is responsible for furnishing any blotting material, if necessary. Aggregate shall meet the following gradation requirements.

SIEVE SIZE	PERCENT PASSING	SAND SEAL
	3/8	
1/2"		100%
3/8"	100%	
No. 4	0-10%	90-100
No.10	0-2%	30-90
No.200		0-5

409.4 METHOD OF MEASUREMENT

Aggregate Primer will be measured by the square yard.

409.5 BASIS OF PAYMENT

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

Payment will be made under:

Item Number	Description	Unit
409000	<i>Aggregate Primer</i>	S.Y.

Separate payment will not be made for blotter material or for rolling of aggregate primer material.

MODIFYING SECTION 423 - HOT MIX ASPHALT

Add the following:

423.7 BASIS OF PAYMENT

423.7.1 Plant mix bituminous pavement will be paid for at the contractor's unit price per square yard. No separate payment will be made for bituminous material, or hydrated lime. No separate payment will be made for tack coat to be applied to the edges of adjacent pavement

Payment will be made under:

Item Number	Description	Unit
423270	<i>HMA SP-IV 2" Complete</i>	S.Y.

No separate measurement or payment will be made for *sawcutting* when paving operations connect to existing pavement. The sawcut shall be a neat clean cut with a smooth transition to the new pavement. Any broken off edges should be corrected by additional sawcuts.

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

ADDING SECTION 499 - CHIPSEAL

ADD the following:

499.1 Single penetration chipseal surfacing shall meet the following requirements.

SIEVE SIZE	PERCENT PASSING	SAND SEAL
	3/8	
1/2"		100%
3/8"	100%	
No. 4	0-10%	90-100
No.10	0-2%	30-90
No.200		0-5

Accepted aggregate material must also meet the following requirements:

1. Aggregate shall consist of gravel, crushed slag, crushed stone or crushed natural limestone rock. Caliche will not be accepted.
2. At least 75% of the Material retained on the No. 4 sieve will be composed of particles that have at least two Fractured Faces. Fractured Faces will be determined in accordance with NMDOT Method FF-1, *Fractured Face Determination for Coarse Aggregate*.
3. The aggregate is free of organic matter, lumps of clay, or other material that prevents thorough coating with asphalt Material.
4. The aggregate is obtained from a source with an **AI of 20** or less when calculated in accordance with Section 910 of STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION NEW MEXICO STATE DEPARTMENT OF TRANSPORTATION 2019 EDITION.

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

The HFE-100P emulsion shall meet the following requirements.

TEST DESCRIPTION	HFE-100P		TEST NO.
	Min.	Max.	
Original Material:			
Viscosity, Saybolt Furol at 50°C (122°F), Sec	50	-	AASHTO T-59
Sieve Test, Retained on No. 20 Sieve, %	-	0.1	AASHTO T-59
Storage Stability Rest, 24 hours, %	-	1.0	AASHTO T-59
Demulsibility, 35mL (1.2 fl oz) 0.10 N, CaCl, %	30	-	AASHTO T-59
Residue from Distillation Test to 204°C (400°F)	65	-	AASHTO T-59
Oil Distillate by Volume of Emulsion, %	-	3	AASHTO T-59
Residue Material:			
Penetration at 25°C (77°F), 100 g, 5 s, 0.1 mm	90	150	AASHTO T-49 ASTM D5
Float Test @ 60°C (140°F), Sec	1200	-	AASHTO T-50 ASTM D139
Ductility 25°C (77°F), 5cm (2 inch)/min	40	-	AASHTO T-51 ASTM D113
Elastic Recovery 10°C (50°F), %	58	-	AASHTO T-301

499.2 METHOD OF MEASUREMENT

Chipseal surface treatment will be measured by the square yard.

499.3 BASIS OF PAYMENT

Payment will be made under:

Item Number	Description	Unit
499000	<i>Single Penetration 3/8" Chipseal</i>	S.Y.

SECTION 15- SUPPLEMENTAL SPECIFICATIONS
LEA COUNTY, NEW MEXICO

CR 27A MARATHON ROAD RECONSTRUCTION
Bid #02 - (20-21)

APPENDIX

Item 247

Flexible Base



1. DESCRIPTION

Construct a foundation course composed of flexible base.

2. MATERIALS

Furnish uncontaminated materials of uniform quality that meet the requirements of the plans and specifications. Notify the Engineer of the proposed material sources and of changes to material sources. The Engineer may sample and test project materials at any time before compaction throughout the duration of the project to assure specification compliance. Use [Tex-100-E](#) material definitions.

- 2.1. **Aggregate.** Furnish aggregate of the type and grade shown on the plans and meeting the requirements of Table 1. Each source must meet Table 1 requirements for liquid limit, plasticity index, and wet ball mill for the grade specified. Do not use additives, such as but not limited to lime, cement, or fly ash to modify aggregates to meet the requirements of Table 1 unless shown on the plans.

Table 1
Material Requirements

Property	Test Method	Grade 1–2	Grade 3	Grade 4 ²	Grade 5
Sampling	Tex-400-A				
Master gradation sieve size (cumulative % retained)	Tex-110-E			As shown on the plans	
2-1/2"		0	0		0
1-3/4"		0–10	0–10		0–5
7/8"		10–35	–		10–35
3/8"		30–65	–		35–65
#4		45–75	45–75		45–75
#40		65–90	50–85		70–90
Liquid Limit, % Max	Tex-104-E	40	40	As shown on the plans	35
Plasticity Index, Max ¹	Tex-106-E	10	12	As shown on the plans	10
Plasticity index, Min ¹		As shown on the plans	As shown on the plans	As shown on the plans	As shown on the plans
Wet ball mill, % Max	Tex-116-E	40	–	As shown on the plans	40
Wet ball mill, % Max increase passing the #40 sieve		20	–	As shown on the plans	20
Min compressive strength, psi	Tex-117-E			As shown on the plans	
lateral pressure 0 psi		35	–		–
lateral pressure 3 psi		–	–		90
lateral pressure 15 psi		175	–		175

- Determine plastic index in accordance with [Tex-107-E](#) (linear shrinkage) when liquid limit is unattainable as defined in [Tex-104-E](#).
- Grade 4 may be further designated as Grade 4A, Grade 4B, etc.

- 2.1.1. **Material Tolerances.** The Engineer may accept material if no more than 1 of the 5 most recent gradation tests has an individual sieve outside the specified limits of the gradation.

When target grading is required by the plans, no single failing test may exceed the master grading by more than 5 percentage points on sieves No. 4 and larger or 3 percentage points on sieves smaller than No. 4.

The Engineer may accept material if no more than 1 of the 5 most recent plasticity index tests is outside the specified limit. No single failing test may exceed the allowable limit by more than 2 points.

- 2.1.2. **Material Types.** Do not use fillers or binders unless approved. Furnish the type specified on the plans in accordance with the following:
- 2.1.2.1. **Type A.** Crushed stone produced and graded from oversize quarried aggregate that originates from a single, naturally occurring source. Do not use gravel or multiple sources.
- 2.1.2.2. **Type B.** Crushed or uncrushed gravel. Blending of 2 or more sources is allowed.
- 2.1.2.3. **Type C.** Crushed gravel with a minimum of 60% of the particles retained on a No. 4 sieve with 2 or more crushed faces as determined by [Tex-460-A](#), Part I. Blending of 2 or more sources is allowed.
- 2.1.2.4. **Type D.** Type A material or crushed concrete. Crushed concrete containing gravel will be considered Type D material. Crushed concrete must meet the requirements in Section 247.2.1.3.2., "Recycled Material (Including Crushed Concrete) Requirements," and be managed in a way to provide for uniform quality. The Engineer may require separate dedicated stockpiles in order to verify compliance.
- 2.1.2.5. **Type E.** Caliche, iron ore or as otherwise shown on the plans.
- 2.1.3. **Recycled Material.** Reclaimed asphalt pavement (RAP) and other recycled materials may be used when shown on the plans. Request approval to blend 2 or more sources of recycled materials.
- 2.1.3.1. **Limits on Percentage.** Do not exceed 20% RAP by weight, when RAP is allowed, unless otherwise shown on the plans. The percentage limitations for other recycled materials will be as shown on the plans.
- 2.1.3.2. **Recycled Material (Including Crushed Concrete) Requirements.**
- 2.1.3.2.1. **Contractor-Furnished Recycled Materials.** Provide recycled materials, other than RAP, that have a maximum sulfate content of 3,000 ppm when tested in accordance with [Tex-145-E](#). When the Contractor furnishes the recycled materials, including crushed concrete, the final product will be subject to the requirements of Table 1 for the grade specified. Certify compliance with [DMS-11000](#), "Evaluating and Using Nonhazardous Recyclable Materials Guidelines," for Contractor furnished recycled materials. In addition, recycled materials must be free from reinforcing steel and other objectionable material and have at most 1.5% deleterious material when tested in accordance with [Tex-413-A](#). For RAP, do not exceed a maximum percent loss from decantation of 5.0% when tested in accordance with [Tex-406-A](#). Test RAP without removing the asphalt.
- 2.1.3.2.2. **Department-Furnished Required Recycled Materials.** When the Department furnishes and requires the use of recycled materials, unless otherwise shown on the plans:
- Department-required recycled material will not be subject to the requirements in Table 1,
 - Contractor-furnished materials are subject to the requirements in Table 1 and this Item,
 - the final product, blended, will be subject to the requirements in Table 1, and
 - for final product, unblended (100% Department-furnished required recycled material), the liquid limit, plasticity index, wet ball mill, and compressive strength is waived.

Crush Department-furnished RAP so that 100% passes the 2 in. sieve. The Contractor is responsible for uniformly blending to meet the percentage required.

2.1.3.2.3. **Department-Furnished and Allowed Recycled Materials.** When the Department furnishes and allows the use of recycled materials or allows the Contractor to furnish recycled materials, the final blended product is subject to the requirements of Table 1 and the plans.

2.1.3.3. **Recycled Material Sources.** Department-owned recycled material is available to the Contractor only when shown on the plans. Return unused Department-owned recycled materials to the Department stockpile location designated by the Engineer unless otherwise shown on the plans.

The use of Contractor-owned recycled materials is allowed when shown on the plans. Contractor-owned surplus recycled materials remain the property of the Contractor. Remove Contractor-owned recycled materials from the project and dispose of them in accordance with federal, state, and local regulations before project acceptance. Do not intermingle Contractor-owned recycled material with Department-owned recycled material unless approved.

2.2. **Water.** Furnish water free of industrial wastes and other objectionable matter.

2.3. **Material Sources.** Expose the vertical faces of all strata of material proposed for use when non-commercial sources are used. Secure and process the material by successive vertical cuts extending through all exposed strata, when directed.

3. EQUIPMENT

Provide machinery, tools, and equipment necessary for proper execution of the work.

3.1. Provide rollers in accordance with Item 210, "Rolling." Provide proof rollers in accordance with Item 216, "Proof Rolling," when required.

3.2. When ride quality measurement is required, provide a high speed or lightweight inertial profiler certified at the Texas A&M Transportation Institute. Provide equipment certification documentation. Display a current decal on the equipment indicating the certification expiration date.

4. CONSTRUCTION

Construct each layer uniformly, free of loose or segregated areas, and with the required density and moisture content. Provide a smooth surface that conforms to the typical sections, lines, and grades shown on the plans or as directed.

Stockpile base material temporarily at an approved location before delivery to the roadway. Build stockpiles in layers no greater than 2 ft. thick. Stockpiles must have a total height between 10 and 16 ft. unless otherwise approved. After construction and acceptance of the stockpile, loading from the stockpile for delivery is allowed. Load by making successive vertical cuts through the entire depth of the stockpile.

Do not add or remove material from temporary stockpiles that require sampling and testing before delivery unless otherwise approved. Charges for additional sampling and testing required as a result of adding or removing material will be deducted from the Contractor's estimates.

Haul approved flexible base in clean trucks. Deliver the required quantity to each 100-ft. station or designated stockpile site as shown on the plans. Prepare stockpile sites as directed. When delivery is to the 100-ft. station, manipulate in accordance with the applicable Items.

4.1. **Preparation of Subgrade or Existing Base.** Remove or scarify existing asphalt concrete pavement in accordance with Item 105, "Removing Treated and Untreated Base and Asphalt Pavement," when shown on

the plans or as directed. Shape the subgrade or existing base to conform to the typical sections shown on the plans or as directed.

When new base is required to be mixed with existing base, deliver, place, and spread the new flexible base in the required amount per station. Manipulate and thoroughly mix the new base with existing material to provide a uniform mixture to the specified depth before shaping.

Proof roll the roadbed in accordance with Item 216, "Proof Rolling," before pulverizing or scarifying when shown on the plans or directed. Correct soft spots as directed.

- 4.2. **Placing.** Spread and shape flexible base into a uniform layer with an approved spreader the same day as delivered unless otherwise approved. Construct layers to the thickness shown on the plans. Maintain the shape of the course. Control dust by sprinkling, as directed. Correct or replace segregated areas as directed, at no additional expense to the Department.

Place successive base courses and finish courses using the same construction methods required for the first course.

- 4.3. **Compaction.** Compact using density control unless otherwise shown on the plans. Multiple lifts are permitted when shown on the plans or approved. Bring each layer to the moisture content directed. When necessary, sprinkle the material in accordance with Item 204, "Sprinkling."

Begin rolling longitudinally at the sides and proceed towards the center, overlapping on successive trips by at least 1/2 the width of the roller unit. Begin rolling at the low side and progress toward the high side on superelevated curves. Offset alternate trips of the roller. Operate rollers at a speed between 2 and 6 mph as directed.

Rework, recompact, and refinish material that fails to meet or that loses required moisture, density, stability, or finish requirements before the next course is placed or the project is accepted. Continue work until specification requirements are met. Perform the work at no additional expense to the Department.

Before final acceptance, the Engineer will select the locations of tests and measure the flexible base depth in accordance with [Tex-140-E](#). Correct areas deficient by more than 1/2 in. in thickness by scarifying, adding material as required, reshaping, recompacting, and refinishing at the Contractor's expense.

- 4.3.1. **Ordinary Compaction.** Roll with approved compaction equipment as directed. Correct irregularities, depressions, and weak spots immediately by scarifying the areas affected, adding or removing approved material as required, reshaping, and recompacting.

- 4.3.2. **Density Control.** Compact to at least 100% of the maximum dry density determined by [Tex-113-E](#), unless otherwise shown on the plans. Maintain moisture during compaction within ± 2 percentage points of the optimum moisture content as determined by [Tex-113-E](#). Measure the moisture content of the material in accordance with [Tex-115-E](#) or [Tex-103-E](#) during compaction daily and report the results the same day to the Engineer, unless otherwise shown on the plans or directed. Do not achieve density by drying the material after compaction.

The Engineer will determine roadway density and moisture content of completed sections in accordance with [Tex-115-E](#). The Engineer may accept the section if no more than 1 of the 5 most recent density tests is below the specified density and the failing test is no more than 3 pcf below the specified density.

- 4.4. **Finishing.** After completing compaction, clip, skin, or tight-blade the surface with a maintainer or subgrade trimmer to a depth of approximately 1/4 in. Remove loosened material and dispose of it at an approved location. Seal the clipped surface immediately by rolling with a pneumatic tire roller until a smooth surface is

attained. Add small increments of water as needed during rolling. Shape and maintain the course and surface in conformity with the typical sections, lines, and grades as shown on the plans or as directed.

Correct grade deviations greater than 1/4 in. in 16 feet measured longitudinally or greater than 1/4 in. over the entire width of the cross-section in areas where surfacing is to be placed. Correct by loosening and adding, or removing material. Reshape and re-compact in accordance with Section 247.4.3., "Compaction."

- 4.5. **Curing.** Cure the finished section until the moisture content is at least 2 percentage points below optimum or as directed before applying the next successive course or prime coat.

- 4.6. **Ride Quality.** This section applies to the final travel lanes that receive a 1 or 2 course surface treatment for the final surface, unless otherwise shown on the plans. Measure ride quality of the base course after placement of the prime coat and before placement of the surface treatment, unless otherwise approved. Use a certified profiler operator from the Department's MPL. When requested, furnish the Engineer documentation for the person certified to operate the profiler.

Provide all profile measurements to the Engineer in electronic data files within 3 days after placement of the prime coat using the format specified in [Tex-1001-S](#). The Engineer will use Department software to evaluate longitudinal profiles to determine areas requiring corrective action. Correct 0.1-mi.sections having an average international roughness index (IRI) value greater than 100.0 in. per mile to an IRI value of 100.0 in. per mile or less for each wheel path, unless otherwise shown on the plans.

Re-profile and correct sections that fail to maintain ride quality until placement of the next course, as directed. Correct re-profiled sections until specification requirements are met, as approved. Perform this work at no additional expense to the Department.

5. MEASUREMENT

Flexible base will be measured as follows:

- **Flexible Base (Complete In Place).** The ton, square yard, or any cubic yard method.
- **Flexible Base (Roadway Delivery).** The ton or any cubic yard method.
- **Flexible Base (Stockpile Delivery).** The ton, cubic yard in vehicle, or cubic yard in stockpile.

Measurement by the cubic yard in final position and square yard is a plans quantity measurement. The quantity to be paid for is the quantity shown in the proposal unless modified by Article 9.2., "Plans Quantity Measurement." Additional measurements or calculations will be made if adjustments of quantities are required.

Measurement is further defined for payment as follows.

- 5.1. **Cubic Yard in Vehicle.** By the cubic yard in vehicles of uniform capacity at the point of delivery.
- 5.2. **Cubic Yard in Stockpile.** By the cubic yard in the final stockpile position by the method of average end areas.
- 5.3. **Cubic Yard in Final Position.** By the cubic yard in the completed and accepted final position. The volume of base course is computed in place by the method of average end areas between the original subgrade or existing base surfaces and the lines, grades, and slopes of the accepted base course as shown on the plans.
- 5.4. **Square Yard.** By the square yard of surface area in the completed and accepted final position. The surface area of the base course is based on the width of flexible base as shown on the plans.

- 5.5. **Ton.** By the ton of dry weight in vehicles as delivered. The dry weight is determined by deducting the weight of the moisture in the material at the time of weighing from the gross weight of the material. The Engineer will determine the moisture content in the material in accordance with [Tex-103-E](#) from samples taken at the time of weighing.

When material is measured in trucks, the weight of the material will be determined on certified scales, or the Contractor must provide a set of standard platform truck scales at a location approved by the Engineer. Scales must conform to the requirements of Item 520, "Weighing and Measuring Equipment."

6. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for the types of work shown below. No additional payment will be made for thickness or width exceeding that shown on the typical section or provided on the plans for cubic yard in the final position or square yard measurement.

Sprinkling and rolling, except proof rolling, will not be paid for directly but will be subsidiary to this Item unless otherwise shown on the plans. When proof rolling is shown on the plans or directed, it will be paid for in accordance with Item 216, "Proof Rolling."

Where subgrade is constructed under this Contract, correction of soft spots in the subgrade will be at the Contractor's expense. Where subgrade is not constructed under this Contract, correction of soft spots in the subgrade will be paid in accordance with pertinent Items or Article 4.4., "Changes in the Work."

- 6.1. **Flexible Base (Complete In Place).** Payment will be made for the type and grade specified. For cubic yard measurement, "In Vehicle," "In Stockpile," or "In Final Position" will be specified. For square yard measurement, a depth will be specified. This price is full compensation for furnishing materials, temporary stockpiling, assistance provided in stockpile sampling and operations to level stockpiles for measurement, loading, hauling, delivery of materials, spreading, blading, mixing, shaping, placing, compacting, reworking, finishing, correcting locations where thickness is deficient, curing, furnishing scales and labor for weighing and measuring, and equipment, labor, tools, and incidentals.
- 6.2. **Flexible Base (Roadway Delivery).** Payment will be made for the type and grade specified. For cubic yard measurement, "In Vehicle," "In Stockpile," or "In Final Position" will be specified. The unit price bid will not include processing at the roadway. This price is full compensation for furnishing materials, temporary stockpiling, assistance provided in stockpile sampling and operations to level stockpiles for measurement, loading, hauling, delivery of materials, furnishing scales and labor for weighing and measuring, and equipment, labor, tools, and incidentals.
- 6.3. **Flexible Base (Stockpile Delivery).** Payment will be made for the type and grade specified. For cubic yard measurement, "In Vehicle" or "In Stockpile" will be specified. The unit price bid will not include processing at the roadway. This price is full compensation for furnishing and disposing of materials, preparing the stockpile area, temporary or permanent stockpiling, assistance provided in stockpile sampling and operations to level stockpiles for measurement, loading, hauling, delivery of materials to the stockpile, furnishing scales and labor for weighing and measuring, and equipment, labor, tools, and incidentals.